BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Division

Schedule - B

NAME OF THE WORK: Construction of RCC drain at Halumuniyappa Layout in ward no. 12, Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate quoted by Sri. R.Shivaram	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
	Earthwork excavation by manual means in ordinary				

4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.complete as per the direction of Engineer-in-charge of the work	Tonne	12.52	54065.83	Rupees Fifty Four Thousand Sixty Five and Eighty Three Paise Only
5	KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. Specification No. KSRB 4.6.9. exceeding 1m in depth. Page No. 15/ Item No. 4.31/ PWD SR 2016-17	Sqm	2011.20	282.62	Rupees Two Hundred Eighty Two and Sixty Two Paise Only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. complete as per the direction of Engineer-in-charge of the work	Sqm	488.70	1456.0	Rupees One Thousand Four Hundred Fifty Six Only
	Disposal of debris to the final place of disposal with all				